



## Work Proposal

Name: Eric Evans  
Address: Town of Millville Park Buildings  
Email: Eevans@mvtown.com

9/25/2021

### Scope of Work

Install (23) zones of irrigation to cover specified areas. Connect into the existing well on site. Town of Millville will cover the cost of marking utilities.

QTY	UoM/Size	Material/Description	Unit Price	Cost
1	Unit	Hunter ICC2 timer w/ expansion modules		
1	Unit	Hunter wireless rain sensor		
1150	Feet	1.5" pvc main line		
2100	Feet	1.25" poly lateral		
3700	Feet	1" poly lateral		
11	Unit	1.5" ball valve		
16	Unit	10" round valve box		
5	Unit	14" standard valve box		
23	Unit	1" Hunter valve M x 1.25" barb		
167	Unit	Hunter 4" PGP Ultra rotor		
85	Unit	Hunter 4" Pro Spray		
85	Unit	Hunter MP nozzle		
1200	Feet	18/13 underground wire		
1	Unit	3/4" quick connect blow out		
1	Unit	Install labor		
1	Unit	Option areas (5 zones)		+\$7,008.00

Total: \$38,184.00  
w/ options: \$45,192.00

**Payment as follows:** Please make checks payable to *Chester River Landscaping* and mail to **26250 Shortly Road, Georgetown, DE 19947**.

Submitted by:  
Chester River Landscaping

Accepted by: \_\_\_\_\_  
Title: \_\_\_\_\_

Date: \_\_\_\_\_ 9/25/21 \_\_\_\_\_

Chase Furst