

Evans Park PB Hardscaping

Minimums: Prospective bidders shall provide company background information referencing their experience in performing such work. References shall be included with their bid, along with proof of license and insurance acceptable to the Town.

Site Work:

Move stone and gravel away from base area prior to installing base for block wall.
Areas to be cleaned daily prior to the end of the workday.

Base:

Base for block wall shall be 8" to 10" deep filled with compacted crushed concrete.

Block Wall:

Block wall shall be approximately 14" to 16" high above grade with cap.
Block wall will have various distances from courts 2-3 feet depending on location.
Blocks to be glued and doweled together.
Weep holes or drainage cloth/tubes shall be placed 6' apart on top of 1st block out of ground.

Type of Stone:

Nicolock Stone 6" Colonial with the color of Chesapeake Blend.

Misc:

Bid job as if no steps are present. The winning bidder and Town will discuss optional design for steps.

Timing for Completion:

Please give your estimated Start and completion time.

Payment:

Shall be negotiated.