Frequency	Maintenance Items
During establishment, as needed (first year)	 Inspect the site after storm event that exceeds 0.5 inches of rainfall. Stabilize any bare or eroding areas in the contributing drainage area including the Wet Pond perimeter area Water trees and shrubs planted in the Wet Pond vegetated perimeter area during the first growing season. In general, water every 3 days for first month, and then weekly during the remainder of the first growing season (April - October) depending on rainfall.
Quarterly or after major storms (>1 inch of rainfall)	Remove debris and blockages Repair undercut, eroded, and bare soil areas
Twice a year	Mowing of the Wet Pond vegetated perimeter area and embankment
Annually	 Shoreline cleanup to remove trash, debris and floatables A full maintenance review Open up the riser to access and test the valves Repair broken mechanical components, if needed
One time -during the second year following construction	Wet Pond vegetated perimeter and aquatic bench reinforcement plantings
Every 5 to 7 years	Forebay sediment removal
From 5 to 25 years	Repair pipes, the riser and spillway, as needed Remove sediment from Wet Pond area outside of forebays

STABILIZATION REQUIREMENTS:

SWM POND AND FOREBAY SIDE SLOPES = DE SEED MIX 9 OR 10 ALL OTHER AREAS WITHIN LOD = DE SEED MIX 12

DISTURBED AREA = 2.42 AC

CLAY LINER SPECIFICATIONS: A CLAY LINER HAVING A MINIMUM COMPACTED THICKNESS OF 12

INCHES WITH AN ADDITIONAL 12 INCH LAYER OF COMPACTED SOIL ABOVE IT. CLAY USED AS POND LINER MUST MEET THE FOLLOWING **SPECIFICATIONS:** a. PERMEABILITY OF 1 X 10⁶ cm/sec USING ASTM D-2434 PROCEDURE.


PROCEDURES. c. LIQUID LIMIT OF NOT LESS THAN 30% USING ASTM D-2216

PROCEDURE. d. CLAY PARTICLES PASSING NOT LESS THAN 30% USING ASTM D-422 PROCEDURE.

b. PLASTICITY INDEX OF NOT LESS THAN 15% USING ASTM D-423/424

e. COMPACTION OF 95% OF STANDARD PROCTOR DENSITY USING ASTM D-2216 PROCEDURE.

2. GEOTECHNICAL ENGINEER IS TO BE ON SITE TO VERIFY MATERIALS BEFORE CLAY LINER IS INSTALLED.



FEB 08, 2019 **AS SHOWN** SKM TRU01-06

WET POND FOREBAY CONSTRUCTION SEQUENCE

Remove sediment from Wet Pond area outside of forebays

- CONTACT DNREC AT (302)739-9944 TO OBTAIN A CONSTRUCTION DEWATERING PERMIT IF DEWATERING IS NECESSARY TO CONSTRUCT PROPOSED IMPROVEMENTS. THE SUSSEX COUNTY CONSERVATION DISTRICT INSPECTOR SHALL INSPECT AND APPROVE ALL DEWATERING OPERATIONS.
- WET PONDS SHOULD ONLY BE CONSTRUCTED AFTER THE CONTRIBUTING DRAINAGE AREA TO THE WET POND IS COMPLETELY STABILIZED.
- CONDUCT PRECONSTRUCTION MEETING WITH AGENCY CONSTRUCTION REVIEWER, CCR, CONTRACTOR, AND OWNER'S REP.
- ASSEMBLE CONSTRUCTION MATERIALS ON-SITE, MAKE SURE THEY MEET DESIGN SPECIFICATIONS, AND PREPARE ANY STAGING AREAS. ENSURE THAT APPROPRIATE COMPACTION AND DEWATERING EQUIPMENT IS AVAILABLE. LOCATE THE PROJECT BENCHMARK AND IF NECESSARY, TRANSFER A BENCHMARK NEARER TO THE WET POND LOCATION FOR USE DURING CONSTRUCTION.
- INSTALL EROSION AND SEDIMENT CONTROLS PRIOR TO CONSTRUCTION, INCLUDING TEMPORARY DEWATERING DEVICES AND STORMWATER DIVERSION PRACTICES. ALL AREAS SURROUNDING THE DRY POND THAT ARE GRADED OR DENUDED DURING CONSTRUCTION MUST BE PLANTED WITH TURF GRASS, NATIVE PLANTINGS, OR OTHER APPROVED METHODS OF SOIL STABILIZATION.
- INSTALL PERMANENT OUTLET CONTROL STRUCTURE AND OUTFALL PIPE WORKING FROM DOWNSTREAM TO UPSTREAM DIRECTION.
- INSTALL DEWATERING DEVICE AND PUMPING PIT.
- 8. EXCAVATE SEDIMENT TRAP AS SHOWN ON PLAN AND INSTALL DEWATERING SKIMMER DEVICE AT LOW FLOW ORIFICE.
- 9. DEWATER, DREDGE, AND REGRADE SEDIMENT TRAP AREA TO DESIGN DIMENSIONS AND ELEVATIONS.
- 10. TEMPORARILY BLOCK WEIR OPENING AT INVERT EL 9.01 UP TO EL 10.00 USING PLYWOOD SHEATHING AND 2"X4" BLOCKING. USE CAULKING AS NECESSARY TO SEAL PLYWOOD TO CONCRETE IN WATERTIGHT CONDITION.
- 11. REMOVE ACCUMULATED SEDIMENT AND BORROW MATERIAL TO AN APPROVED OFFSITE LOCATION, OR STOCK PILE ON STE, STABILIZE STOCK PILE ACCORDING TO THE PERMANENT SEEDING NOTES ON DRAWING T1.2.
- 12. NOTIFY THE PERSON RESPONSIBLE FOR STORMWATER SYSTEM CONSTRUCTION REVIEW AT LEAST 3 DAYS PRIOR TO THE START OF STORMWATER SYSTEM CONSTRUCTION; STORMWATER FACILITIES MUST BE REVIEWED THROUGH OUT THEIR CONSTRUCTION.


- BOTTOM AND SIDE SLOPES OF THE WET POND AND FOREBAYS. CONSTRUCT FOREBAYS AT THE
- 16. TOPSOIL, SEED AND MULCH THE SIDE SLOPES AND DISTURBED AREAS AROUND THE POND. SOIL STABILIZATION MATTING SHALL BE USED ON ANY SLOPES 3:1 OR STEEPER.
- 19. CLEAR AND STRIP THE EMBANKMENT AREA TO THE DESIRED SUB-GRADE.
- 20. CONSTRUCT THE EMBANKMENT AND ANY INTERNAL BERMS USING ACCEPTABLE MATERIAL IN 8 12 INCH LIFTS, COMPACT THE LIFTS WITH APPROPRIATE EQUIPMENT. CONSTRUCT THE EMBANKMENT
- BOTTOM AND SIDE SLOPES OF THE WET POND AND FOREBAY. CONSTRUCT FOREBAY AT THE
- ELEVATION MUST BE PERMANENTLY STABILIZED IN ACCORDANCE WITH THE VEGETATIVE STABILIZATION SPECIFICATION ON THE APPROVED SEDIMENT AND STORMWATER MANAGEMENT
- 23. CONSTRUCT DECK FOR SEATING AREA. CONTRACTOR SHALL TAKE PRECAUTIONS TO PRESERVE THE INTEGRITY OF THE GCL AND PLACE AN ADDITIONAL 12" WIDE X 12" THICK (24" TOTAL THICKNESS) OF GCL AROUND PERIMETER OF PILE.
- COVERAGE, DEWATERING OPERATIONS IN THE WET POND MAY CEASE.
- 25. REMOVE SKIMMER AND CONVERT OUTFALL TO PERMANENT OUTFALL STRUCTURE.


- FOR PURPOSES OF PERIODIC SITE REVIEWS.
- . THE SUSSEX CONSERVATION DISTRICT SHALL BE NOTIFIED WITHIN 30 BUSINESS DAYS IF THE PROPERTY OWNERSHIP IS TRANSFERRED TO A NEW PERSON
- THE DNREC SEDIMENT AND STORMWATER PROGRAM AND/OR THE SUSSEX CONSERVATION DISTRICT MAY SEEK ENFORCEMENT ACTION AGAINST ANY OWNER DEEMED NEGLIGENT IN FULFILLING THE OPERATION AND MAINTENANCE REQUIREMENTS OF THE DELAWARE SEDIMENT AND STORMWATER
- MAINTENANCE, OR IF MODIFICATIONS TO THE FACILITY ARE DESIRED.
- TREES SHALL NOT BE PLANTED, AND SHALL BE REMOVED IF FOUND GROWING, ON AND WITHIN 15 FEET OF ALL POND EMBANKMENTS, ON POND SLOPES
- 3. WHEN THE FACILITY IS EXCAVATED TO REMOVE ACCUMULATED SEDIMENT, THE DISPOSAL AREA SHALL BE PERMANENTLY STABILIZED SO THAT IT DOES
- 9. BEFORE ANY EARTHWORK OR EXCAVATION TAKES PLACE, THE CONTRACTOR SHALL CALL MISS UTILITY AT 811 OR 1.800.282.8555 AT LEAST 48 HOURS PRIOR TO CONSTRUCTION, TO HAVE ALL EXISTING UTILITIES MARKED ONSITE.

- 13. EXCAVATE/GRADE UNTIL APPROPRIATE ELEVATION AND DESIRED CONTOURS ARE ACHIEVED FOR THE PROPOSED INFLOW POINTS.
- 14. INSTALL SPECIFIED INLET PROTECTION AS EACH BASIN IS INSTALLED.
- 15. INSTALL RIP-RAP OUTLET PROTECTION AS SPECIFIED ON ALL POND INLET PIPES.
- 17. CONTACT SUSSEX CONSERVATION DISTRICT FOR SITE INSPECTION
- 18. CONVERT TEMPORARY SEDIMENT TRAP TO PERMANENT EXTENDED DETENTION WET POND WITH FOREBAY. REFER TO POND CODE 378 CONSTRUCTION SPECIFICATIONS.
- 21. EXCAVATE/GRADE UNTIL APPROPRIATE ELEVATION AND DESIRED CONTOURS ARE ACHIEVED FOR THE PROPOSED INFLOW POINTS. INSTALL GCL PER PROJECT GEO-TECHNICAL ENGINEER.
- 22. STABILIZE EXPOSED SOILS AND THE GCL WITH 12" OF TOPSOIL AND WITH THE APPROVED SEED MIXTURES APPROPRIATE FOR THE WET POND PERIMETER AREA. ALL AREAS ABOVE THE NORMAL POOL
- 24. AFTER ALL PLANTED AREAS WITHIN THE WET POND HAVE ACHIEVED A 70% OR GREATER VEGETATIVE
- 26. CONDUCT FINAL INSPECTION WITH OWNER'S REPRESENTATIVE. AGENCY SITE REVIEWER, CCR. AND ADDRESS ALL PUNCH LIST ITEMS.


STANDARD OPERATION AND MAINTENANCE NOTES

- . THE DNREC SEDIMENT AND STORMWATER PROGRAM AND/OR THE SUSSEX CONSERVATION DISTRICT RESERVE THE RIGHT TO ENTER PRIVATE PROPERTY
- REGULATIONS.
- . THE SUSSEX CONSERVATION DISTRICT SHALL BE CONTACTED IF A CONCERN ARISES REGARDING A MANAGEMENT FACILITY, BEFORE ANY NON-ROUTINE
- ANY DESIGN MODIFICATIONS MADE TO THE STORMWATER SYSTEM SHALL REQUIRE THE CREATION OF A NEW POST CONSTRUCTION STORMWATER MANAGEMENT PLAN AND/OR OPERATIONS AND MAINTENANCE PLAN, WITH APPROVAL OF THE PLAN(S) BY THE SUSSEX CONSERVATION DISTRICT.
- FOR ALL STORMWATER EASEMENT AREAS (I.E., ACCESS, MAINTENANCE, OR OFFSITE) AND THE MINIMUM 15-FOOT WIDE ACCESSWAYS TO ALL STORMWATER FACILITIES AND THEIR STRUCTURAL COMPONENTS, REGULAR MOWING SHALL BE PERFORMED TO KEEP THE GRASS 6" OR LESS; NO TREES OR SHRUBS SHALL BE PLANTED, AND ANY FOUND GROWING SHALL BE REMOVED; AND NO PERMANENT STRUCTURES, SUCH AS FENCES OR SHEDS, SHALL BE LOCATED WITHIN THE EASEMENT OR ACCESSWAY.
- OR SAFETY BENCHES, AND WITHIN 10 FEET OF STRUCTURAL COMPONENTS, SUCH AS PIPE INLETS.
- NOT RECREATE AN EROSION PROBLEM. ANY MATERIAL TAKEN OFFSITE SHALL STILL BE UTILIZED OR DISPOSED OF IN AN APPROVED DNREC MANNER.
- 10. THE OWNER / DEVELOPER/ PROPERTY OWNER SHALL BE RESPONSIBLE FOR OPERATION AND MAINTAINANCE OF EACH POST CONSTRUCTION STORMWATER MANAGEMENT FACILITY.










FEB 08, 2019 AS SHOWN SKM



TIDEWATER UTILITIES INC. UTILITY NOTES

- 1. PRESSURE PIPE FOR WATER MAINS 4" AND GREATER SHALL BE IN ACCORDANCE WITH AWWA C900 DR18 FOR PVC PIPE OR AWWA C909 CLASS 235 FOR PVCO PIPE.
- 2. FITTINGS FOR WATER MAINS OF 4" AND GREATER SHALL BE MECHANICAL JOINT DUCTILE IRON PROVIDED BY TYLER UNION OR APPROVED EQUAL. MECHANICAL JOINT RESTRAINT SHALL BE MEGALUG® SERIES 2000PV PRODUCED BY EBAA IRON INC. OR APPROVED EQUAL
- 3. DUCTILE IRON PIPE SHALL BE CLASS 150 IN ACCORDANCE WITH AWWA C151; AWWA C111 WITH CEMENT LINING AND BITUMINOUS COATING.
- 4. PRESSURE PIPE FOR 2" AND LESS SHALL BE HIGH DENSITY POLYETHYLENE PIPE IN ACCORDANCE WITH AWWA C901 FABRICATED FROM MATERIAL WITH A CLASSIFICATION OF ASTM D1248. THE PIPE SHALL BE COPPER TUBE I.D., SDR 9.
- 5. WATER VALVES FOR MAINS 4" AND GREATER SHALL BE RESILIENT WEDGE GATE VALVES CONFORMING TO AWWA C509. BURIED VALVES TO BE FITTED WITH A 2" OPERATING NUT WITH A NON-RISING STEM. VALVES SHALL BE AMERICAN FLOW CONTROL, SERIES 500 OR APPROVED EQUAL
- 6. VALVE BOXES SHALL BE CAST IRON 2 PIECE SCREW TYPE ADJUSTABLE WITH "WATER" CAST IN THE COVER PROVIDED BY TYLER UNION MODEL 564-S OR APPROVED EQUAL.
- VALVES SHALL BE PLACED A MAXIMUM DISTANCE OF 2 FEET FROM A TEE OR CROSS UNLESS A CONFLICT
- 8. SADDLES FOR PRESSURE WATER MAIN SHALL BE FORD STAINLESS STEEL BANDED SADDLES FS202 SERIES.
- 9. CURB STOPS SHALL BE FORD FB1700 BALLCORP SERIES WITH CC THREADS.
- 10. ALL WATER MAIN SHALL BE INSTALLED WITH TRACER WIRE FOR LOCATION EQUIPMENT CONNECTION. TRACER WIRE SHALL BE #12 SOLID COPPER CORE, BLUE COLOR, WITH THHN OR EQUAL INSULATION. TRACER WIRE TO BE RAN CONTINUOUSLY ALONG AND DIRECTLY ADHERED TO WATER MAIN ON TOP OF WATER MAIN UTILIZING INDUSTRIAL ADHESIVE DUCT TAPE. TRACER WIRE TO BE ADHERED TO PIPE WITH A MINIMUM OF 3 LOCATIONS ON ANY LENGTH OF PIPE TO INSURE ACCURATE WATER MAIN LOCATION. LOCATION WIRE TO BE PULLED UP THROUGH ALL VALVE BOXES FOR LOCATION EQUIPMENT CONNECTION.
- 11. BURIAL DEPTH OF WATER MAINS TO BE A MINIMUM OF 48".
- 12. ALL WATER MAINS TO HAVE METAL CONDUCTOR TYPE DETECTOR TAPE INSTALLED 2' DIRECTLY ABOVE AND CONTINUOUSLY ALONG WATER MAIN. DETECTOR TAPE SHALL BE TERRA-TAPE BY ALLEN SYSTEMS OR APPROVED
- 13. FIRE HYDRANTS SHALL BE AMERICAN DARLING B-62-B. SEE LOCAL HYDRANT SPECIFICATIONS FOR PUMPER NOZZLE AND HOSE NOZZLE INFORMATION.
- 14. BACKFLOW PREVENTERS, WHERE REQUIRED, SHALL MEET ALL REQUIREMENTS OF ASSE STANDARD 1013 AND AWWA C506, LATEST REVISION. BACKFLOW PREVENTERS SHALL BE WATTS SERIES 909 HW, CONBRACO SERIES 40-200 OR APPROVED EQUAL.
- 15. NEWLY INSTALLED WATER MAIN SHALL BE DISINFECTED IN ACCORDANCE WITH AWWA C651 STANDARDS, LATEST REVISION BEFORE ACCEPTANCE CAN BE GRANTED.
- 16. WATER MAINS SHALL HAVE A MINIMUM 10' HORIZONTAL AND 18" VERTICAL SEPARATION FROM SANITARY
- 17. TIDEWATER UTILITIES, INC. IS TO BE NOTIFIED 48 HOURS PRIOR TO COMMENCEMENT OF CONSTRUCTION.
- 18. A PRE-CONSTRUCTION MEETING IS TO BE HELD BEFORE ANY CONSTRUCTION ACTIVITIES CAN COMMENCE.
- 19. WATER METERS ARE TO BE OBTAINED FROM TIDEWATER UTILITIES, INC.
- 20. ALL WATER SYSTEM COMPONENTS ARE TO BE INSTALLED IN ACCORDANCE WITH THE LATEST TIDEWATER UTILITIES CONSTRUCTION STANDARDS AND APPLICABLE AWWA STANDARDS.
- * "APPROVED EQUAL" DEFINED AS APPROVED BY TIDEWATER UTILITIES, INC.


ENGINEER'S CERTIFICATION:

I, ROBERT J. PALMER, HEREBY CERTIFY THAT I AM A REGISTERED PROFESSIONAL ENGINEER IN THE STATE OF DELAWARE AND THAT THIS PLAN WAS EITHER PREPARED BY ME OR UNDER MY DIRECTION. TO THE BEST OF MY KNOWLEDGE AND BELIEF, THIS PLAN COMPLIES WITH THE APPLICABLE STATE AND LOCAL REGULATIONS AND ORDINANCES. MY LICENSE NUMBER IS 11563, AND EXPIRES ON JUNE 30, 2022.

ROBERT J. PALMER, P.E. BEACON ENGINEERING, LLC 23318 CEDAR LANE


11/04/2021

GEORGETOWN, DELAWARE 19947




SITE DATA

BRADLEY A. ABSHER



WATER PLAN NOTES:

- 16" X 6" TAPPING TEE (APPROXIMATE LOCATION. SEE PLAN.)
- (V-1) 6" VALVE
- BORE AND JACK 51 LF 12" SCH 40 STEEL CASING PIPE. STEEL CASING SHALL
- HAVE A MINIMUM WALL THICKNESS OF 0.375". (X-1) CROSSING 1 STA: 0+11.60 L 39.88 FT
- (5) 10' X 30' BORING PIT
- (6) 6" X 4" REDUCER STA: 0+43.58 L 39.45 FT
- (7) (V-2) 4" VALVE
- (8) (X-2) CROSSING 2 STA: 0+45.32 L 64.49 FT
- 9 90° BEND
- 1 TAP, METER PIT, AND WATER SERVICE, TYP. REFER TO TIDEWATER
 - STANDARD DETAILS A-1 AND A-3 ON SHEET UT3.2, TYP.
- 2" PERMANENT BLOW OFF STA: 3+17.34 L 150.88 FT. REFER TO TIDEWATER STANDARD DETAIL A-4 ON SHEET UT3.2.
- (12) 4" 90° BEND
- (H-1) HYDRANT ASSEMBLY. STA: 0+40.68 L 23.68 FT. REFER TO TIDEWATER STANDARD DETAIL A-7 ON SHEET UT3.2. FACE STEAMER NOZZLE TO ADJACENT CURB.
- (14) 6" TEE STA: 0+40.68 L 39.51 FT
- (15) 6" X 4" REDUCER STA: 0+40.68 L 19.81 FT
- (16) (V-3)6" VALVE
- (17) (V-4) 4" VALVE
- (18) 22.5° BEND
- (19) 22.5° BEND (X-3) CROSSING 3 STA: 0+31.21 R 98.07 FT
- 21) 22.5° BEND
- (22) 90° BEND
- (23) 2" PERMANENT BLOW OFF STA: 1+87.34 R 151.31 FT. REFER TO TIDEWATER STANDARD DETAIL A-4 ON SHEET UT3.2.
- 24) 10' X 20' RECEIVING PIT. TEMPORARY CONSTRUCTION EASEMENT IS
- (X-4) CROSSING 2 STA: 0+37.32 R 134.42 FT





JUL 20, 2020


1" = 30'


SKM


M:\Projects\TRU01-06 - Millville Square\Construction Docs\DWGs\Utility DWG\TRU01-06 UTILITIES.dwg Nov 04 , 2021 - 12:00pm, (Sarah)















WATER CROSSING (X-1)
H-1"=30" V-1"=3"

WATER CROSSING (X-2)
H-1"=30' V-1"=3'

WATER CROSSINGS (X-3 & X-4)

H-1"=30' V-1"=3'




12

13

WATER MAIN PROFILE A

H-1"=30' V-1"=3'





WATER MAIN PROFILE B


H-1"=30' V-1"=3'


0 30 60 90 FEET


Date: JUL 20, 2020
| Scale: 1" - 30'
| Dwn.By: SKM | Proj.No.: TRU01-06


































12

13







Date: JUL 20, 2020
Scale: NO TO SCALE
Dwn.By: SKM
Proj.No.: TRU01-06

UT3.2

16